



PROJECT PROFILE

B&J Catalano | New Tailings Storage Facility (TSF) Re-Instatement

CLIENT

B&J Catalano

PROJECT

TSF Lift Pipeline
Re-Instatement

LOCATION

Golden Grove, Yalgoo WA

REQUIREMENT

Relocate pipe for tails dam
lift and reinstate

PIPE WORK

- Install 25 Sweep Bends and 13 reducers
- Install 52 x 160mm 6m lengths

CONTRACT

Day rates

ADDITIONAL WORKS

- Lift pipe from temporary wall onto new wall
- Install all droppers and spigot clamps
- Supply and install 1,200m of DN170 Mega Flo for seepage
- Install DN160 seepage outflow pipes around the dam
- Installation of spigot droppers

SERVICES AND EQUIPMENT PROVIDED

- Supervisor, Polywelder and Operators
- Supervisors vehicle and welding truck c/w generator
- 2 x Manitou Telehandlers and spreader bars
- 8.5 ton Excavator and pipe roller slings
- 3 x HF350 Polywelders
- Extrusion welders

