



PROJECT PROFILE

GNT Resources | Borefield Installation

CLIENT

GNT Resources

PROJECT

Primary Borefield Installation

LOCATION

Dalgaranga, Murchison WA

REQUIREMENT

Install 10.5km Borefield Pipeline

PIPE WORK

- 8.1km 315mm PN8
- 600m 355mm PN8
- 1.8km 280mm PN10

CONTRACT

Day rates

ADDITIONAL WORKS

- Harvest and load 150 x 315mm PN10 x 20m lengths
- Unload and stock pile pipe along the pipeline corridor for station welding
- Supply, fabricate and install 9 pipeline breather tee's
- Connect bore headworks
- Install culvert at road crossings

SERVICES AND EQUIPMENT PROVIDED

- Supervisor, Polywelder and Operators
- Supervisors vehicle and welding truck c/w generator
- 2 x Manitou Telehandlers
- Tracstar 500 Polywelder and data logger
- 2 x Polyhorse pipe racking system with Power Assist
- 2 x HF350 Polywelders
- Sea Container storage facility

